

Callaway Stadium – Artificial Turf Replacement Project

Artificial Turf Replacement Project - RFP (1/15/2025)

801 Dallis Street, LaGrange, Ga 30240

Quote/Bid #1 – Replace the Artificial Turf System at Callaway Stadium (Scope of Work):

- Per the Site Plan Provided (see attached Site Plan).
- Provide and install all required/necessary materials, supplies, labor, equipment, machinery, etc. for a complete artificial turf replacement project, per the scope of work.
- All work shall be coordinated with Troup County Staff.
- Provide a copy of all manufacturer’s product warranties and the contractor’s written warranty covering all labor, installation, and workmanship.
- Clean-up & dispose of all construction debris and/or trash, per Local/State/Federal regulations.
- Protect surrounding areas from damage & debris.
- Removal and disposal of the existing artificial turf system and associated materials.
- Installation of the new artificial turf system with the following minimum specifications:
 - Meets 1 Turf Concept Standard,
 - Installation of 25mm EPP shock pad with vertical and lateral drainage – 25 yr. warranty,
 - Field has to have a GMAX below 120 for 10 years or life of warranty whichever is longer,
 - HIC (head injury criteria) needs to be below 1000 for the life of the field,
 - 60 oz blended fiber with monofilament and slit-film with a thatch layer,
 - 2 inches in length for all fibers,
 - Alternating contrasts in color panels (Green),
 - No logos but lined for football/ soccer/ lacrosse,
 - Rubber filling,
 - Provide a 10 year maintenance program,
 - Provide a 10 year non-prorated warranty.