

## LOCKER ROOM AND RESTROOM FLOOR COATING

THE MIKE DANIEL RECREATION CENTER

1220 LAFAYETTE PARKWAY

LAGRANGE, GA 30241

### Scope of Work

The men's area is approximately 635 square feet.

The Women's area is approximately 670 square feet.

- Remove all toilets and partitions and store.
- Mechanically remove the existing coating and 4" cove base.
- Cut 1" x 1" keyways around the perimeter of areas and next to all drains. This strengthens the edges to prevent failure.
- Waterproof the drains and shower pans with latex sealant.
- Saw cut control joints and cracks and prepare them to receive a 2 component polyurea joint filler.
- Vacuum the prepared substrate and install blue painters' tape to protect areas that will not receive coating at that time.
- Repair voids and holes on the concrete with Pumadur urethane cement per manufacturer's specifications.
- Install 4" cove base using Micor DL and 1882 Topcoat.
- Install Urethane Cement @ 1/8" thickness with quartz aggregate for slip resistance. Broadcast to rejection to achieve a nonskid surface.
- Once cured, vacuum excess sand and buff substrate to take care of any imperfections.
- Apply Micor DL Epoxy and broadcast color quartz to rejection to achieve a nonskid surface.
- Recut joints and fill them with a 2-part polyurea per manufacturer's specifications. Install with a plural component pump.
- Install grout coat with Micor DL and broadcast color quartz to rejection.
- Topcoat with Micor 1882 Epoxy.
- Clean up work area.
- Reinstall toilets and partitions.

BID RESPONSE SHEET

LOCKER ROOM AND RESTROOM FLOOR COATING

THE MIKE DANIEL RECREATION CENTER

May 25, 2021 2:00 P.M

Total Price \_\_\_\_\_

Date Available to Start Project \_\_\_\_\_

Number of Days to Complete \_\_\_\_\_

Company \_\_\_\_\_

Address \_\_\_\_\_

City, State, Zip \_\_\_\_\_

Telephone Number \_\_\_\_\_

Email Address \_\_\_\_\_

Signature \_\_\_\_\_

Print Name \_\_\_\_\_